

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-083-21712-00-00  
Spot: SWNENWNE Sec/Twnshp/Rge: 31-23S-24W  
400 feet from N Section Line, 1787 feet from E Section Line  
Lease Name: FRANK Well #: 31-2  
County: HODGEMAN Total Vertical Depth: 4900 feet

Operator License No.: 32204  
Op Name: REDLAND RESOURCES, LLC  
Address: 6001 NW 23RD ST  
OKLAHOMA CITY, OK 73127

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4642		2sx
DVT	4.5	1377		260 SX
PROD	4.5	4885		410 SX
SURF	8.625	238		170 SX
TI	2.375	4649		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/13/2015 10:00 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Revd. from: DAVID HICKMAN Company: REDLAND RESOURCES, LLC Phone: (620) 253-6588

Proposed Plugging Method: Set CIBP @ 4642' w/ 2sx cement. Run tubing to 1620' and circulate cement to surface. Check backside with cement to 500psi.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/13/2015 10:00 AM KCC Agent: LARRY HARRIS

Actual Plugging Report:

Set CIBP @ 4642' w/ 2sx cement. Run tubing to 1631' and circulate cement w/ 130sx. Pull tubing and top off w/ 31sx cement. Checked backside w/ cement to 800psi it was full.

Perfs:

Top	Bot	Thru	Comments
4716	4720		
4692	4704		

Remarks: CEMENT: 60/40 POZMIX 4% GEL BY ALLIED CEMENTING

Plugged through: TBG

District: 01 RECEIVED

JUL 13 2015  
KCC DODGE CITY

Signed

*[Handwritten Signature]*  
SA  
TECHNICIAN  
KCC WICHITA

JUL 24 2015  
RECEIVED