

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-083-21882-00-00  
Spot: N2SENE SW Sec/Twnshp/Rge: 33-23S-24W  
1859 feet from S Section Line, 3010 feet from E Section Line  
Lease Name: BARBARA Well #: 33-11  
County: HODGEMAN Total Vertical Depth: 4900 feet

Operator License No.: 32204  
Op Name: REDLAND RESOURCES, LLC  
Address: 6001 NW 23RD ST  
OKLAHOMA CITY, OK 73127

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	4630		2sx cement
DVT	4.5	1418	0	270sx cement to 0'
PROD	4.5	4894		175 SX
SURF	8.625	222		150 SX
T1	2.375	4621		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/10/2015 10:30 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Revd. from: DAVID HICKMAN Company: REDLAND RESOURCES, LLC Phone: (620) 253-6588

Proposed Plugging Method: Set CIBP @ 4630' w/ 2sx cement. Run tubing to 1650' circulate cement to surface. Check backside with cement to 500psi.

Plugging Proposal Received By: WADE KLAUS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/10/2015 10:30 AM KCC Agent: LARRY HARRIS

Actual Plugging Report:

Set CIBP @ 4630' w/ 2sx cement. Run tubing to 1661' circulated cement to surface with 130sx cement. Pulled tubing and topped of with 20sx cement. Pumped 13.5sx cement down backside held 500psi.

Perfs:

Top	Bot	Thru	Comments
4700	4704	CSG	
4681	4686	CSG	

Remarks: CEMENT: 60/40 POZMIX 4% GEL BY ALLIED CEMENTING

Plugged through: TBG

District: 01

KCC DODGE CITY

JUL 13 2015

RECEIVED

SM

Signed

*Larry Harris*  
SA (TECHNICIAN)  
KCC WICHITA

7/29/15 com

JUL 24 2015

RECEIVED