

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-053-20533-00-00
Spot: SWSNW Sec/Twnshp/Rge: 32-15S-8W
3294 feet from S Section Line, 3348 feet from E Section Line
Lease Name: HELWICK Well #: 4
County: ELLSWORTH Total Vertical Depth: 2655 feet

Operator License No.: 5047
Op Name: RUPE OIL COMPANY, INC.
Address: 111 WHITTIER # 1000 PO BOX 783010
WICHITA, KS 67207

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	2250		
PROD	4.5	2654	912	0 SX
SURF	8.625	246		150 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/01/2015 9:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMES HARRIS Company: MIKE'S TESTING & SALVAGE INC. Phone: (620) 562-0895

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 07/01/2015 12:45 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SET CIBP AT 2250' AND CAP WITH 2 SX'S CEMENT. CUT CASING AT 912', PULL UP SOME AND PUMP 35 SX'S COMMON CEMENT WITH 2% CC. PULL CASING ON UP TO 600' AND WAIT 1 HOUR. TAG CEMENT WITH SWAB BAR AT 624'. PUMP 35 SX'S THRU CASING AT 600', PULL CASING TO 300' AND CIRCUALTE CEMENT TO SURFACE. PULL CASING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
2572	2580		CSG
2460	2466		CSG
2292	2298		CSG

Remarks: 60-40 POZ, 4% GEL. LOG TECH OF KS #8512. COPELAND #C41313. THIS WELL WAS A TA NOV - OPERATOR DECIDED TO PLUG.

Plugged through: CSG

7/29/15 ccm

District: 02

Signed *Virgil Clothier*
(TECHNICIAN)

KCC WICHITA

JUL 14 2015

RECEIVED/