

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-141-20075-00-00  
Spot: NWENWNW Sec/Twnshp/Rge: 10-10S-15W  
4950 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: HOGAN Well #: 2  
County: OSBORNE Total Vertical Depth: 3615 feet

Operator License No.: 32278  
Op Name: TENGASCO, INC.  
Address: 1327 NOOSE RD PO BOX 458  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3614		150 SX
SURF	8.625	260		140 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/02/2015 8:00 AM  
Plug Co. License No.: 32332 Plug Co. Name: FISCHER WELL SERVICE, INC.  
Proposal Rcvd. from: GARY WAGNER Company: TENGASCO INC Phone: (785) 625-6374

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
Squeezed 1222' - 1223' w/375 sx cement.  
Production perforations: 3182' - 3588'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/02/2015 11:15 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3520' and pumped 50 sx cement w/200 # hulls. Pulled tubing to 2760' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1380' and pumped 90 sx cement to circulate cement to surface. Pulled all tubing and topped off 4 1/2" casing w/25 sx cement. Shut in pressure 300 psi. Hooked to 8 5/8" x 4 1/2" annulus and pumped 25 sx cement. Shut in pressure 200 psi.

GPS: 39.20454N -098.98827W

Perfs:

Top	Bot	Thru	Comments
3586	3588		
3582	3588		
3235	3401		
3182	3185		

Remarks: QUALITY OILWELL CEMENTING

Plugged through: TBG

7/29/15 CKM

District: 04

Signed \_\_\_\_\_

*Pat Bedore*

(TECHNICIAN)

CM

Received  
KANSAS CORPORATION COMMISSION

Form CP-2/3

JUL 10 2015

CONSERVATION DIVISION  
WICHITA, KS

JUL 06 2015