

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-151-20608 -00-00 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Kansas Petroleum, Inc. OPERATOR'S LICENSE NO. 5023

ADDRESS 225 N. Market, Suite 310, Wichita, KS PHONE # (316) 267-2266

LEASE (FARM) Weir "C" WELL NO. 2 WELL LOCATION 50' N. C NE NW COUNTY Pratt

SEC. 16 TWP. 29 RGE. 11 (C) of (W) TOTAL DEPTH 3102' PLUG BACK TD 3073'

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" -28# SET AT 317' CEMENTED WITH 225 SACKS

CASING SIZE 5 1/2" SET AT 3096' CEMENTED WITH 150 SACKS

PERFORATED AT 2674-77' & 2666-68' (Indian Cave)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set cast iron bridge plug @ 2650' w/2 sks cement. Anticipate casing cut & removal @ 2000'. Top plug 4 sks cotton seed hulls, 10 sks gel, 50 sks 60/40 pos cement, 10 sks gel, 1 sk cotton seed hulls, 8 5/8" wiper plug, 100 sks 60/40 pos cement. Displace to 10'. Cut off casing 4' below ground, weld on plate.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN July 19, 1989, 8:00 A.M.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Warren Richardson PHONE # (316) 775-3613

ADDRESS 2907 Lakeshore Drive, Augusta, Kansas 67010

PLUGGING CONTRACTOR Pratt Well Service LICENSE NO. 5893

ADDRESS Box 847, Pratt, Kansas 67124 PHONE # (316) 672-2531

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: James [Signature]
(Operator or Agent)

DATE: 7-12-89

RWD
07-12-89

1



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
MARGALEE WRIGHT COMMISSIONER
JUDITH MCCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

THIS NOTICE

OCT 12 1989

EXPIRES

July 12, 1989

NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

Kansas Petroleum, Inc.
225 N. Market, Ste. 310
Wichita, KS 67202

Weir "C" #2
50'N C NE NW
Sec. 16-29S-11W
Pratt County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht

Shari Feist Albrecht
Director

District: #1 304 W. McArtor
Dodge City, KS 67801
(316) 225-6760