

15-097-20032-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER NA

LEASE NAME Pyle-Taylor

WELL NUMBER 1  
100' W of C

SPOT LOCATION N/2 SW/4

SEC. 1 TWP. 28S RGE. 19 (X) or (W)

COUNTY Kiowa

Date Well Completed 9-8-67

Plugging Commenced 8-26-85

Plugging Completed 8-26-85

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR TGT Petroleum Corp.

ADDRESS 209 E. William - Wichita, Ks.

PHONE # (316) 262-6489 OPERATORS LICENSE NO. 5118

Character of Well oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist. #6 - Dodge City, Ks.

Is ACO-1 filed? No If not, is well log attached? Not avail.

Producing formation Mississippi Depth to top 4825 bottom TD T.D. 4857

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	378'	None
				4 1/2"	4856	"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Spotted cement plug from 1190' to 750', followed by 4 sacks of gel from 750' to 90'. cemented from 90' to top of casing/w/8 sacks cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor TGT Petroleum Corp. License No. 5118

Address 209 E. William - Wichita, Ks.

STATE OF Kansas COUNTY OF Sedgwick, ss.

B. Lynn Herrington (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me, God.

(Signature) B. Lynn Herrington

(Address) 209 E. William - Wichita, Ks.


RECEIVED  
STATE CORPORATION COMMISSION

SEP 3 1985  
9-3-85

SUBSCRIBED AND SWORN TO before me this 29th day of August, 1985

CONSERVATION DIVISION  
Wichita, Kansas

My Commission expires: May 17, 1989



Notary Public  
Judith K. Moser

15-097-20032-0000

ORIGINAL

STENCILED

KANSAS GEOLOGICAL SOCIETY  
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
KANSAS GEOLOGICAL SOCIETY BUILDING  
508 EAST MURDOCK - WICHITA, KANSAS

SEC 18 100'

COMPANY CHICK M, FARHA

SEC. 1 T. 28 R. 19W  
LOC. 100' W of N/2 SW

FARM Pyle-Taylor NO. 1

TOTAL DEPTH 4857'

COUNTY Kiowa


COMM. 8-23-67

COMP. 9-8-67

SHOT OR TREATED

CONTRACTOR Garvey Drlg. Co.

ISSUED 12-16-67



CASINO

20	10	
15	B 5/8	378' w/250 sx cem.
12	6	
13	5 1/2	4857' w/200 sx cem.

ELEVATION 2257' GL

PRODUCTION 48 BOPD &  
WTR. MISS 4828-51

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface Sand	135
Blue Shale	379
Shale and Sand	656
Red Bed and Shale	1195
Anhydrite	1230
Shale and Shells	1585
Shale	2089
Lime and Shale	2319
Anhydrite, Lime and Shale	2506
Lime and Shale	4426
Lime	4441
Lime and Shale	4595
Lime	4700
Lime and Shale	4816
Mississippi	4857
RTD	4857

SCOUT TOPS

Lansing K.C.	4247
Mississippi	4825

RECEIVED  
STATE CORPORATION COMMISSION

SEP 3 1985

CONSERVATION DIVISION  
Wichita, Kansas