

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-173-20,410-0000

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name Winco of Kansas

Complete Address 1502 N. Broadway, Wichita, Ks. 67214

Lease Name Marie M. McClallen Well No. # 1

Location SW SW SW Sec. 36 Twp 27-S Rge. 2 (~~East~~) (West)

County Sedgwick Total Depth 3489'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor H & H Casing Pulling

Address Box 563, Burrton, Ks. 67020 License No. # 880

Operation Completed: Hour: 5:10 PM Day: 1 Month: 10 Year: 19 81

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

8 5/8" sur. csg. 522' cemt./400 sx. 4 1/2" csg. 3484' cemt.

PBTD 3010' Perf. 2990' to 2992'

Set bottom Bridge 2900', 15' rock, dumped 4 sx. cemt./bailer

Shot & pulled 2315' 4 1/2" csg. Left 1169' of csg. in hole.

United Cementing & Acid Co. Inc. pumped 3 sx. hulls, 6 sx. gel,

200 sx. cemt. 4% gel, down 8 5/8" sur. csg. PP 500# SIP 200#

Fluid level before pump 150'

RECEIVED
STATE CORPORATION COMMISSION

OCT 5 1981

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: Don Thompson
Conservation Division Agent

10-5-1981

INVOICED

DATE 11-18-81

INV. NO. 284-E