

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely

Take Required Affidavit

Mail or Deliver Report to

Conservation Division

State Corporation Comm.

245 North Water

Wichita, KS 67202

Pratt County, Sec. 22 Twp. 29S Rge. 13 ~~XX~~/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines \_\_\_\_\_  
NW/4 SW/4

Lease Owner Woolsey Petroleum Corporation  
Lease Name Matthew Novotny "C" Well No. 1  
Office Address 300 W. Douglas, Suite 400, Wichita, KS  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
dry hole

Date Well completed 12/17 19 82  
Application for plugging filed 12/17 19 82  
Application for plugging approved 12/17 19 82  
Plugging commenced 12/17 19 82  
Plugging completed 12/17 19 82


Reason for abandonment of well or producing formation \_\_\_\_\_  
No commercial quantity of oil or gas encountered.  
If a producing well is abandoned, date of last production \_\_\_\_\_  
19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Steve Durant

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Total depth 4780 feet. Set first plug at 720 feet with 140 sacks of 50-50 poz mix cement, 4% Gel and 3% Calcium Chloride; set second plug at 300 feet with 80 sacks; 20 sacks and a bridge at 40 feet and 10 sacks in the rathole. Job completed at 5:30 p.m. on December 17, 1982.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kaw Drilling Co., Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss. contractor  
K. S. Martin, President of Kaw Drilling Co., Inc. (employer of contractor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
K. S. Martin, President 1010 Union Center  
(Address) Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 20th day of December, 1982.

My commission expires 12-10-83

[Signature]  
Notary Public

RECEIVED  
STATE CORPORATION COMMISSION

DEC 21 1982

CONSERVATION DIVISION  
Wichita Kansas



OPERATOR: Woolsey Petroleum Corporation  
 CONTRACTOR: Kaw Drilling Co., Inc.  
 WELL NAME: #1 Matthew Novotny "C"  
 LOCATION: NW/4 SW/4 Sec. 22-29S-13W  
 Pratt County, Kansas  
 SPUD DATE: December 3, 1982  
 COMPLETION DATE: December 17, 1982


1024	1056	Shale
1708	2046	Shale and Corral
2205	2411	Shale and Shell
4385	4475	Lime and Shale

Spud hole at 9:30 a.m. on December 3, 1982. Drilled 277 feet of 15 inch hole. Ran 6 joints of 10 3/4 inch casing. (Tallied at 261.98 feet.) Set at 273 feet with 250 sacks common cement, 3% Calcium Chloride and 2% Gel. Plug down at 3:30 p.m. on December 3, 1982.


Total depth 4780 feet. Set first plug at 720 feet with 140 sacks of 50-50 poz mix cement, 4% Gel and 3% Calcium Chloride; set second plug at 300 feet with 80 sacks; 20 sacks and a bridge at 40 feet and 10 sacks in the rathole. Job completed at 5:30 p.m. on December 17, 1982.

STATE OF KANSAS        )  
                                   )    SS  
 COUNTY OF SEDGWICK )


I, K. S. Martin, President of Kaw Drilling Co., Inc., being first duly sworn and upon my oath, state that: I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

  
 K. S. Martin, President

SUBSCRIBED AND SWORN to before me on this 20th day of December, 1982.

  
 Mary Susan Whaley, Notary Public

My Commission Expires:  
 December 10, 1983



RECEIVED  
 STATE CONSERVATION COMMISSION

DEC 21 1982

CONSERVATION DIVISION  
 Wichita, Kansas