

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21,328-0p-00

LEASE NAME Novotny

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1-21

702 Ft. from S Section Line

618 Ft. from E Section Line

SEC. 21 TWP. 29S RGE. 13 ~~XX~~ or (W)

LEASE OPERATOR Texas Energies, Inc.

ADDRESS P.O. Box 947 Pratt, KS 67124

COUNTY Pratt

PHONE# (316) 672-7514 OPERATORS LICENSE NO. 5087

Date Well Completed 11-03-83

Character of Well Oil

Plugging Commenced 12-06-88

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12-09-88

The plugging proposal was approved on 12-08-88 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? Yes if not, is well log attached? _____

Producing Formation Viola Depth to Top 4544 Bottom 4554 T.D. 4800

Show depth and thickness of all water, oil and gas formations.

RECEIVED

OIL, GAS OR WATER RECORDS

CASING RECORDS STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
				16	48	None
				8 5/8	381	None
				4 1/2	4776	214

JAN 5 1989
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Plugged bottom inside 4 1/2" csg by dumping sand to 4443'; Placed 4 sxs common cement on top with dump bailer; Pulled 4 1/2" csg; Placed top plugs by pumping down 8 5/8" csg as follows: 15 bbls. fresh water with 300# hulls; 25 bbls. fresh water with 10 sxs gel; 50 sxs 60-40 poz mix 6% gel; 43 bbls. mud with 36+ viscosity (6 sxs of gel); 3 bbls. fresh water with 100# hulls; dropped
(If additional description is necessary, use BACK of this form.)

8 5/8" wiper plug; 100 sxs 60-40 poz mix 6% gel. Maximum pressure 500#, ISIP 350#, 3 bpm.
Name of Plugging Contractor Texas Energies, Inc. License No. 5087

Address P.O. Box 947 Pratt, KS 67124


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Texas Energies, Inc.

STATE OF Kansas COUNTY OF Pratt, ss.

Mark P. Stevenson (Employee of Operator) or (~~Operator~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mark P. Stevenson

(Address) P.O. Box 947 Pratt, KS 67124



SUBSCRIBED AND SWORN TO before me this 4th day of January, 19 89

Dorothy M. Furgason
Notary Public

My Commission Expires Feb 6, 1989

ORIGINAL