

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-151-20234-00-04
 LEASE NAME Harris

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER #2
1650' Ft. from S Section Line
1980' Ft. from W Section Line
 SEC. 18 TWP. 29 RGE. 13 (E) or (W)

LEASE OPERATOR Trans Pacific Oil Corporation
 ADDRESS 100 S. Main, Suite 200, Wichita, KS 67202
 PHONE# (316) 262-3596 OPERATORS LICENSE NO. 9408

COUNTY Pratt
 Date Well Completed _____
 Plugging Commenced 3/20/02
 Plugging Completed 3/21/02

Character of Well Oil
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)
 The plugging proposal was approved on 3/20/02 (date)
 by Scott Alberg (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____
 Producing Formation _____ Depth to Top 3908' Bottom 4580' T.D. 4584'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0	401	8-5/8"	401'	0
	Production	0	4580	5-1/2"	4580'	2159.05'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Set bridge plug at 3860'. 2 sx cement, cut pipe at 2150'. Pulled to 800', spot 10 sx gel and 50 sx cement. Pulled to 420', 50 sx cement. Pulled to 40', 10 sx cement. Circulated cement to surface.

Name of Plugging Contractor D.S. & W. Well Servicing, Inc. License No. 6901
 Address P.O. Box 231, Claflin, KS 67525

RECEIVED

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Trans Pacific Oil Corporation
 STATE OF Kansas COUNTY OF Barton, ss.

MAR 26 2002
 KCC WICHITA

Joseph F. Strube (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Joseph F. Strube
 (Address) P.O. Box 231, Claflin, KS 67525

KAREN J. MITCHELL
 Notary Public - State of Kansas
 My Appt. Expires 4/13/02

SUBSCRIBED AND SWORN TO before me this 25th day of March, 2002

Karen J. Mitchell
 Notary Public

My Commission Expires: 4/13/02

OR