


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pratt County, Sec. 18 Twp. 29S Rge. 13 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C W/2 W/2 SE/4

Lease Owner Mid-Continent Energy Corp.
Lease Name Harris Well No. 1
Office Address One Twenty Bldg, #712, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plot

Date Well completed August 28, 1979
Application for plugging filed August 28, 1979
Application for plugging approved August 28, 1979
Plugging commenced August 28, 1979
Plugging completed August 28, 1979
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production
_____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen, Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 14682'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	280'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pumped 50 sacks cement through drill pipe to 600 feet. Pumped 40 sacks cement through drill pipe to 260 feet. Pushed plug and 1 sack hulls to 40 feet and pumped 20 sacks cement through drill pipe with pump truck to base of well cellar. Plugged rat hole with 4 sacks cement. Plugged water well with 1 sack cement.

STATE RECEIVED
SEP - 7 1979
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Graves Drilling Co., Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
John C. Graves (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

910 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of September, 19 79

Betty Brandt
Betty Brandt Notary Public.

My commission expires May 9, 1983

ROTARY DRILLERS' LOG

OPERATOR: Mid-Continent Energy Corp.
Suite 712, One Twenty Building
Wichita, Kansas

COMMENCED: August 15, 1979

CONTRACTOR: Graves Drilling Co., Inc.
910 Union Center
Wichita, Kansas 67202

COMPLETED: August 28, 1979

CASING RECORD: 7 Jts. 280' of new 10-3/4"
cemented with 260 sacks

LOCATION: Harris No. 1
C W/2 W/2 SE/4
Section 18-298-13W
Pratt County, Kansas

0 - 240	Sand & shale
240 - 950	Red bed
950 - 1580	Shale
1580 - 4505	Shale & lime
4505 - 4514	Lime
4514 - 4682	Lime & chert
4682	Rotary Total Depth

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.


GRAVES DRILLING CO., INC.

By *John Graves*
President

RECEIVED
STATE CORPORATION COMMISSION
SEP - 7 1979
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss.
SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public, this 6th day of
September, 1979.



Betty Brandt
Betty Brandt Notary Public

My commission expires: May 9, 1983