

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 5-151-21,524

LEASE NAME Leak

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1
110' W & 110' S of
SPOT LOCATION NE NE SE

SEC. 6 TWP 29S RGE. 13 (E) or (W)

LEASE OPERATOR Penquin Petroleum, Inc.

COUNTY Pratt

ADDRESS 1250 KSB&T Bldg., Wichita, KS 67202

Date Well Completed 12-13-84

PHONE # (316) 267-3393 OPERATORS LICENSE NO. 5234

Plugging Commenced 12-12-84

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12-13-84

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? DIST #1 (STEVE DURANT)

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	360'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Plug @ 810' w/50 sx., Plug @ 390' w/40 sx., Plug @ 40' w/10 sx., Rat Hole 15 sx.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Rains & Williamson Oil Co., Inc. License No. 682
Address 435 Page Court, 220 W. Douglas, Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.


Wilson Rains, President of Rains & Williamson Oil Co. (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Wilson Rains
(Address) 435 Page Court, 220 W. Douglas

SUBSCRIBED AND SWORN TO before me this 17 day of December, 19 84

My Commission expires: 10-4-87

Notary Public
Juanita M. Green



RECEIVED
STATE CORPORATION COMMISSION

IAN 17 1985

CONSERVATION DIVISION
Wichita, Kansas

DRILLER'S LOG

COMPANY: Penguin Petroleum, Inc.

SEC. 6 T. 29S R. 13W

WELL NAME: Leak #1

LOC. 110' W & 110' S of
NE NE SE
COUNTY: Pratt

RIG NO. #3

TOTAL DEPTH 4600'

ELEVATION 1953 GL 1962 KB

COMMENCED: 12-5-84

COMPLETED: 12-13-84

CONTRACTOR: Rains & Williamson Oil Co., Inc.

CASING RECORD:

SURFACE: 8 5/8" @ 360' w/225 sx. 60/40 poz., 2% gel, 3% cc.

PRODUCTION: D&A

LOG

(Figures Indicate Bottom of Formations)

Redbed & Shale	1240
Shale & Shells	1456
Shale	1900
Shale & Lime	2160
Lime & Shale	2585
Shale & Lime	3005
Lime & Shale	3590
Shale	4600
<u>ROTARY TOTAL DEPTH</u>	<u>4600</u>

STATE OF Kansas)

COUNTY OF Sedgwick)

SS:

I, Wilson Rains, President of Rains & Williamson Oil Co., Inc.

upon oath state that the above and foregoing is a true and correct copy of the log of the well.

Leak #1 well.

Wilson Rains

Wilson Rains

Subscribed and sworn to before me this 17 day of December, 1984.

My Appointment Expires:

10-4-87

Juanita M. Green
Juanita M. Green

