


STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Give All Information Completely  
Make Required Affidavit  
Mail & Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

### WELL PLUGGING RECORD



Locate well correctly on above Section Flat

Pratt County, Sec. 5 Twp. 29 Rge. 13 (E) (W)  
 Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SE SW NW  
 Lease Owner Rine, Roberts & Murphy  
 Lease Name Hertlein Well No. 1  
 Office Address 320 Central Bldg., Wichita 2, Kansas  
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
 Date well completed 10/26/50 19. 50  
 Application for plugging filed 10/26/50 19.  
 Application for plugging approved 10/26/50 19.  
 Plugging commenced 10/26/50 12:30 P.M. 19.  
 Plugging completed 10/26/50 2:00 P.M. 19.  
 Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19.  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes, via telephone

Name of Conservation Agent who supervised plugging of this well C. D. Stough, Dist. Plugging Supervisor  
 Producing formation Depth to top Bottom Total Depth of Well 4653! Feet  
 Show depth and thickness of all water, oil and gas formations.

#### OIL, GAS OR WATER RECORDS

#### CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface	Sand	0	190!			
Red Bed & Shells	same	190!	335!	10-3/4"	329!	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud from total depth to 300!  
 Halliburton Plug @ 300! w/ 25 Sx. Cement.  
 Heavy mud from plug @ 300! to 25!  
 Halliburton Plug @ 25! w/10 Sx. Cement.

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 NOV - 1 1950 11-01-50  
 CONSERVATION DIVISION  
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to The R. W. Rine Drilling Co.  
 Address 320 Central Bldg., Wichita 2, Kansas


STATE OF Kansas, COUNTY OF Sedgwick, ss.  
 E. H. Sloyer (employee of owner) or (owner or operator) of the above-described well,  
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *E. H. Sloyer*  
 Secretary  
 320 Central Bldg., Wichita 2, Kans.  
 (Address)

SUBSCRIBED AND SWORN TO before me this 30th day of October, 19 50

*R. M. Green*  
 Notary Public.

My commission expires Dec. 29, 1952



Hertlein Well No. 1

SE SE SW  
Sec. 5-29S-13W  
Pratt County  
Kansas

Contractor: The R. W. Rine Drilling Company  
Started 10/12/50 Finished 10/26/50

	LOG	
Sand	0 - 190	
Red Bed - Shells	190 - 335	10-3/4" Csg. @ 329 w/ 225 Sx.
Red Bed	335 - 550	
Red Bed - Shale - Shells	550 - 1400	Syfo @ 1000' - 1/2°
Shale - Shells	1400 - 1645	
Salt - Shale	1645 - 1690	
Shale - Shells	1690 - 1910	
Lime	1910 - 2255	Syfo @ 2000' - 1°
Lime - Shale	2255 - 3422	Syfo @ 2500' - 0°
Lime	3422 - 3632	Syfo @ 3000' - 1/2°
Lime - Shale	3632 - 3785	Syfo @ 3500 - 0.K.
Lime - Shale - Sand	3785 - 3895	
Lime	3895 - 4010	Syfo @ 4000' - 0.K.
Lime - Shale	4010 - 4072	
Lime	4072 - 4450	
Chert - Shale	4450 - 4495	
Lime - Chert - Shale	4495 - 4513	
Lime - Shale	4513 - 4535	
Core #1	4535 - 4545	8' recovery
Core #2	4545 - 4550	1' recovery - saturated sand
Shale - Sand	4550 - 4557	
Shale	4557 - 4599	
Shale - Chert	4599 - 4633	
Lime	4633 - 4653	D & A

Tops: K.C. Lansing Brown	3931 (-1978)
K.C. Lansing White	3950 (-1997)
Base Kansas City L.	4308 (-2355)
Mississippi	4427 (-2474)
Viola	4451 (-2498)
Simpson Shale	4518 (-2565)
Simpson Dolomite	4531 (-2578)
Simpson Sand	4540 (-2587)
Arbuckle	4634 (-2681)

RECEIVED  
STATE CORPORATION COMMISSION  
NOV - 1 1950  
CONSERVATION DIVISION  
Wichita, Kansas

State of Kansas )  
County of Sedgwick ) ss

I, E. H. Sloyer, do hereby certify that the above is a true and accurate log of the Hertlein Well No. 1, located in the SE SE SW of Sec. 5-29S-13W, Pratt, County, Kansas.

*E. H. Sloyer*  
Secretary

Subscribed to and sworn before me this 30th day of October, 1950.

My commission expires Dec. 29, 1952

*R. M. Green*  
Notary Public

PLUGGING  
WELL SEC 5-29-13W  
BOOK PAGE 39 LINE 15