


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Pratt County. Sec. 3 Twp. 29S Rge. 13W EXW  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
1830' FNL and 510' FEL

Lease Owner Texas Oil and Gas Corp.  
Lease Name Mason Well No. 1  
Office Address 200 West Douglas, Suite 300, Wichita, Ks.  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Dry Hole



Locate well correctly on above  
Section Plat

Date Well completed April 8, 1977  
Application for plugging filed Verbal Application 19  
Application for plugging approved Verbal Approval 19  
Plugging commenced April 8, 1977  
Plugging completed April 8, 1977  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Buddy Metz  
Producing formation Depth to top Bottom Total Depth of Well 4810'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

STATE CORPORATION COMMISSION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
APR 14 1977 4-14-77 CONSERVATION DIVISION Wichita Kansas				10-3/4"	265'	None
				8-5/8"	1047'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy rotary mud from 4,810 ft. (rotary total depth) to 360 ft. Set plug at 360 ft. and cemented with 35 sacks cement. Filled hole with heavy rotary mud from 360 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 15 sacks cement, 5 sacks cement in rat hole.

Plugging operations accomplished utilizing Allied Oil Well cementing pump truck through 4-1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Allied Cementing Co., Inc.  
Box 31, Russell, Kansas 67665

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Dean Britting, Agent (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting  
200 North Main, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of April, 1977



Elsie Willison - Notary Public.

My commission expires June 30, 1978

KANSAS GEOLOGICAL SOCIETY API NO. - 15-151-20,367  
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
 KANSAS GEOLOGICAL SOCIETY BUILDING  
 508 EAST MURDOCK - WICHITA, KANSAS


COMPANY Texas Oil and Gas Corp.

SEC. 3 T. 29S R. 13W  
 LOC. 1830' FNL & 585' FEL

FARM Mason NO. 1

COUNTY Pratt

TOTAL DEPTH 4,810'  
 COMM. March 24, 1977 COMP. April 8, 1977  
 SHOT OR TREATED  
 CONTRACTOR H-30, Inc.  
 ISSUED April 13, 1977



CASING 20 15 12 13	10-3/4" 265' cemented w/250 sxs cement 8-5/8" 1046' cemented w/150 sxs cement 6 5	ELEVATION 1929 GR.  PRODUCTION
--------------------------------	--	--------------------------------------

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand and Shale	265'
Shale	2,120'
Shale and Lime	2,225'
Lime and Shale	2,944'
Shale and Lime	2,963'
Lime and Shale	3,112'
Lime	3,297'
Lime and Shale	3,710'
Lime	4,558'
Lime and Chert	4,756'
Lime	4,810'
Rotary Total Depth	4,810'

RECEIVED  
 STATE CORPORATION COMMISSION  
 APR 15 1977  
 CONSERVATION DIVISION  
 Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

*Dean Britting*  
 Dean Britting

State of Kansas }  
 County of Sedgwick } ss:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 13th. day of April, 1977.

*Elsie Willison*  
 Elsie Willison - Notary Public

My Commission Expires:  
 June 30, 1978

