

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-151-22,013-00.00

LEASE NAME OMO

WELL NUMBER 1-17

4920 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 17 TWP. 29 RGE. 13 (W)

COUNTY PRAIRIE

Date Well Completed _____

Plugging Commenced 7-29-92

Plugging Completed 7-31-92

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR F. G. HOLL CO.

ADDRESS P.O. Box 780167

PHONE# (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-30-92 (date)

by DUANE RANKIN ON LOCATION 7-31-92 KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation _____ Depth to Top _____

PBTD: Bottom 4600 T.D. 4858

Show depth and thickness of all water, oil and gas formations.

PERFS: 4709-4718

4610-4628

4522-4560

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	277	1 3/4	277	0
		0	4856	4 1/2	4856	2292 ft. - 54 jts.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

SET B.P. AND DUMPED 25X CEMENT ON TOP. CUT CSG. AT 2292' -
PULLED 54 JTS. HALLIBURTON TOP HOLE PLUGGED WITH
HULLS, GEL, CIBP- CEMENT. 60-40 P02-6% GEL.
8-3-92: 27' DOWN TO CEMENT- FILLED TO TOP WITH SAND.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PRAIRIE WELL SERVICE INC. License No. 5893

Address P.O. Box 847 PRAIRIE, KS. 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F. G. HOLL CO.

STATE OF KANSAS COUNTY OF PRAIRIE, ss.


JUDY BERRY

PLUGGING CONTRACTOR

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) P.O. Box, Inc. AUG 7 1992



SUBSCRIBED AND SWORN TO before me this 5th day of August 1992

Dorothy M. Ferguson
 Notary Public

My Commission Expires: Feb. 6, 1993


Oil Well Rod & Tubing Service • Single & Double Drum Units • Truck Mounted Spudders • Power Tubing Tongs • Tubing Crews, Etc.

Experienced Crews
Heavy Pole Masts
Telescoping Derricks
Properly Insured



In Business Since 1946

Carl R. Gates, President
Alma Gates, Sec.-Treas.
723 South Ninnescah
Pratt, Kansas 67124



STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - OMO #1-17

Located: NE NE NE, Section 17-29S-13W, Pratt County, Kansas

OWNER: F. G. Holl Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: October 21, 1990

COMPLETED: October 30, 1990

TOTAL DEPTH: 4858'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 280 Surface Soil and Red Bed	Ran 7 joints 13 3/4", 48# casing. 265.89' pipe set at 277' K.B.
280 - 695 Shale, Red Bed	Cemented with 275 sacks 60/40 Pozmix with 2% gel and 3% cc.
695 - 1968 Shale	Plug down at 4:30 PM, 10-21-90, by Howco.
1968 - 4549 Lime and Shale	
4549 - 4600 Mississippi	
4600 - 4858 Lime and Shale	Ran 117 joints 4 1/2" casing. 4848.94' pipe set at 4856' K.B. Cemented with 100 sacks Lite and 125 sacks F. G. Holl mix, 500 gal. super flush and 20 bbl. salt flush. Plug down at 8:15 AM, 10-30-90, by Howco.

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 10 1992

CONSERVATION DIVISION
WICHITA, KS

Deviation Surveys: 3/4° at 4500'
3/4° at 4858'