

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Pratt SEC. 16 TWP. 29S RGE. 13W E/W  
Location as in quarters or footage from lines:  
SE NW NW

+			

Locate Well  
correctly on above  
Section Platt.

Lease Owner F & M OIL CO., INC.  
Lease Name Foster "B" Well No. 1  
Office Address 422 Union Center, Wichita, Kansas 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): Dry  
Date Well Completed August 9, 1982  
Application for plugging filed August 9, 1982  
Plugging commenced August 9, 1982  
Plugging completed August 9, 1982  
Reason for abandonment of well or producing formation Dry

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice V. Leslie  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4840'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Set 1st plug @ 700' w/60 sxs  
Set 2nd plug @ 310' w/40 sxs  
Set 3rd plug @ 40' w/10 sxs  
10 sxs in the rat hole, 5 sxs in the water well  
Plug down @ 5:30 pm (8-9-82)

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor \_\_\_\_\_

STATE OF Kansas COUNTY OF Sedgwick, SS.  
R. D. Messinger (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) R. D. Messinger  
422 Union Center, Wichita, Ks. 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of August 19 82

Shirley A. Gallegos  
Notary Public

Commission Expires: 12-24-84

Shirley A. Gallegos AUG 26 1982



CONSERVATION DIVISION  
Wichita, Kansas

CONTRACTOR'S WELL LOG

OPERATOR: F & M OIL CO., INC.  
CONTRACTOR: Union Drilling Co., Inc.  
LEASE NAME: Foster "B" #1  
LOCATION: SE NW NW Section 16-29S-13W  
Pratt County, Kansas  
COMMENCED: July 30, 1982  
COMPLETED: August 9, 1982


---

0	134	Sand	Set 8-5/8" @ 324' w/250 sxs common
134	340	Sand & redbed	cement 3% CC, 2% gel.
340	1100	Redbed & shale	
1100	4156	Shale	
4156	4281	Shale & lime	
4281	4382	Lime & shale	
4382	4686	Lime	
4686	4703	Chert	
4703	4710	Chert & sand	
4710	4764	Lime & sand	
4764	4840	Lime	
4840		RTD	

---

We certify that the above foregoing is a true and correct copy of the log on the Foster "B" #1, SE NW NW Section 16-29S-13W, Pratt County, Kansas.

Union Drilling Co., Inc.

  
R. D. Messinger

STATE OF KANSAS     )  
                                  ) SS  
COUNTY OF SEDGWICK )

Subscribed and sworn to before me, a Notary Public in and for the aforesaid County and State as of this 23rd day of August, 1982.

My appointment expires:

12-24-84

  
Shirley A. Gallegos-Notary Public

