



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
APR 2 - 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Crow of Da Mac Drlg Co has this

date requested permission to plug the following described well:

Mr. Crow guarantees payment of the plugging fee.

Operator's full Name: Clinton Oil Co

Complete Address: Box 1201 Wichita, KS

Lease Name: R. Harris Well No. 1-V

Location: S/2 NE/SW Sec. 18 Twp. 29S Rge. 13 (E)(W) W

County: Pratt Total Depth 4584 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Crow was instructed to plug the well as follows:

400 ft 8 5/8 surface cemented with 300 sacks. Pump plug,  
25 sacks cement to 375 ft. Mud to 40 ft, plug, 1/2 sack  
hulls, 10 sacks cement to surface. 2 sacks cement in rat  
hole.

Pumped by Halliburton Cementing Co Great Bend, KS

Very truly yours,

Conservation Division Agent