

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Gordan Keen of McClure Oil Company has this
date requested permission to plug the following described well:

Mr. Keen guarantees payment of the plugging fee.

Operator's full Name: McClure Oil Company

Complete Address: 1301 Plaza Bldg., Wichita, Kansas

Lease Name: Inslee Well No. # 1

Location: NW NW SW Sec. 23 Twp. 29 Rge. 11 (E)(W) W

County Pratt Total Depth 4691' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Keen was instructed to plug the well as follows:

411' of 8 5/8" surface pipe, cement circulated with 320 sacks. Fill
hole with drilling mud to 300', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
JUL 28 1966
CONSERVATION DIVISION
Wichita, Kansas