

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

APR 13 1964
 04-13-64
 CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Leighton Young of Austral Oil Company Inc. has this date requested permission to plug the following described well:

Mr. Young guarantees payment of the plugging fee.

Operator's full Name: Austral Oil Company Inc.

Complete Address: 300 San Jacinto Bldg., Houston 2, Texas

Lease Name: John H. Collett Well No. # 1

Location: C SW NW Sec. 30 Twp. 29 Rge. 11 (E) (W) W

County Pratt Total Depth 4751 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Young was instructed to plug the well as follows:

416' of 8 5/8" surface pipe, cement circulated. Fill hole with drilling mud to 250', 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 10 sacks to base cellar. Bridge and cement rat and mouse hole with 4 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent