



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 19 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bishop of Leben Drlg. Co. has this

date requested permission to plug the following described well:

Mr. Bishop guarantees payment of the plugging fee.

Operator's full Name: Leben et al

Complete Address: 200 W. Douglas Wichita, Ks

Lease Name: Becker C Well No. 1

Location: C NW/NE Sec. 12 Twp. 29s Rge. 11 (E)(W) W

County: Pratt Total Depth 3800 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Bishop was instructed to plug the well as follows:

299 ft 8 5/8 surface pipe cemented with 275 sacks. Fill

hole to 275 ft, plug, 1/2 sack hulls, 35 sacks cement. Mud

to 40 ft, plug, 1/2 sack hulls, 10 sacks cement to surface.

2 sacks cement in rat hole.

Very truly yours,


Conservation Division Agent