

To: 1 040588  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

11-7 API NUMBER 15- 151-22,065-00-00 71  
NW SW NE, SEC. 15, T. 29 S, R. 11 W/E

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5056  
Operator: F.G. Holl Company  
Name &  
Address P.O. Box 780167  
Wichita, KS 67278-0167

3630 feet from S section line  
2310 feet from E section line  
Lease Name Hirt Well # 1-15  
County Pratt 155.49  
Well Total Depth 4784 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sterling Drilling Company License Number 5142  
Address P.O. Box 129, Sterling, KS 67579

Company to plug at: Hour: 3:45 p.m. Day: 7 Month: 11 Year: 19 91  
Plugging proposal received from Vaughn Thompson  
(company name) Sterling Drilling Company (phone) 316-278-2131

were: to fill hole with heavy mud and spot cement through drill pipe  
1st plug at Arbuckle with 50 sx cement, 2nd plug at 700' with 50 sx cement,  
3rd plug at 290' with 40 sx cement, 4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 5 p.m. Day: 7 Month: 11 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 700' with 50 sx cement,  
2nd plug at 300' with 40 sx cement,  
3rd plug at 60' with 10 sx cement,  
4th plug to circulate rathole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 12 1991  
Conservation Division  
Wichita Kansas

Remarks: Used 60/40 Pozmix 6% gel by HOWCO.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**  
Observe this plugging.

DATE 12-4-91  
INV. NO. 33924

Signed Stephan J. Pifer  
(TECHNICIAN)

FOR KCC USE:

EFFECTIVE DATE: 10-22-91  
DISTRICT #  
SSAT Yes  No

State of Kansas 15- 151-22,065 -00-09  
NOTICE OF INTENTION TO DRILL

FORM C-1 7/91  
FORM MUST BE TYPED  
FORM MUST BE SIGNED  
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date: October 28, 1991  
month day year

Spot: NW SW NE Sec 15 Twp 29 S, Rg 11W East West

OPERATOR: License # 5056  
Name: F. G. Holl Company  
Address: 6427 E. Kellogg P.O. Box 780167  
City/State/Zip: Wichita, Ks. 67278-0167  
Contact Person: Elwyn H. Nagel  
Phone: (316) 684-8481

3630' FSL feet from South line of Section  
2310' FEL feet from East line of Section  
IS SECTION X REGULAR IRREGULAR

(NOTE: Locate well on the Section Plat on Reverse Side.)  
County: Pratt  
Lease Name: HIRT Well # 1-15  
Field Name: Sandy

CONTRACTOR: License #: 5142  
Name: Sterling Drilling Co.

Is this a Prorated/Spaced Field? ... yes X no  
Target Formation(s): Lansing, Miss., Simr., Sd.  
Nearest lease or unit boundary: 990'  
Ground Surface Elevation: 1820' Est. feet MSL

Well Drilled For: Well Class: Type Equipment:  
X Oil ... Enh Rec X Infield X Mud Rotary  
X Gas ... Storage ... Pool Ext. ... Air Rotary  
... OWWO ... Disposal ... Wildcat ... Cable  
... Seismic; ... # of Holes ... Other

Water well within one-quarter mile: ... yes X no  
Public water supply well within one mile: ... yes X no  
Depth to bottom of fresh water: 180'  
Depth to bottom of usable water: 200'

If OWWO: old well information as follows:  
Operator: RECEIVED  
Well Name: STATE COMMISSION  
Comp. Date: STATE Old Total Depth

Surface Pipe by Alternate: X 1 2  
Length of Surface Pipe Planned to be set: 250'  
Length of Conductor pipe required: NA  
Projected Total Depth: 4790'  
Formation at Total Depth: Arbuckle

Directional, Deviated or Horizontal well? ... yes X no  
If yes, true vertical depth:  
Bottom Hole Location: Wichita, Kansas

Water Source for Drilling Operations:  
X well ... farm pond ... other  
DWR Permit #: (Applied for by Sterling Drilg...  
Will Cores Be Taken?: ... yes X no  
If yes, proposed zone:

Exp. 4/17/92  
The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.  
It is agreed that the following minimum requirements will be met:

220' Alt. I Req.

AFFIDAVIT

1. Notify the appropriate district office prior to spudding of well:

Pusher Vaughn Thompson  
SPUD DATE 10-28-91 INIT.  
LENGTH SURFACE PLANNED 260 8 2/8  
RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. bbls. when done bbls.  
RATHOLED AHEAD? Y N SIZE HOLE  
SURFACE PIPE @ CONDUCTOR  
ANHYDRITE T- B- ELEVATION  
TD 4784 FORMATION and 4735  
RAN PIPE @ DV TOOL ALT II DONE  
SX SX Y N  
Arbuckle Plug @ 150 Ft. W/ 50 SX  
Hug./Council @ Ft. W/ SX  
Anhydrite Base @ 700 Ft. W/ 50 SX  
1/2 Base Anhy. @ Ft. W/ SX  
1/2, 1/2 Plug @ Ft. W/ SX  
Bottom Surface @ 300 290 Ft. W/ 40 SX  
40' Plug @ 60 Ft. W/ 10 SX  
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 40 SX  
WATER WELL SX (Irr. Well Pond Hauling)  
TECHNICIAN R. C. DATE 10-28-91  
TYPE OF CEMENT 60/40 poz 60#  
STARTING TIME 3:45 (AM/PM) DATE 11-7-91  
COMPLETION TIME 5:00 (AM/PM) DATE 11-7-91  
CEMENT COMPANY Hance  
Dink intasod