

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C-E/2-SE/4, Sec. 22, T 29 S, R 13 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151 -20,737 -00-00

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5135

Lease Name Lee Well # 3

Operator: John O. Farmer
Name & P. O. Box 352
Address Russell, KS 67665

County Pratt

Well Total Depth 4706 feet 152.95

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 210

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 9:30 am Day: 4 Month: May Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Deacon Pulley

(company name) Rockhold (phone) 316-792-2506

were: 4 1/2 set at 4706' Top perf 4654-59

1st plug sand back to 4600' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 2 sx hulls

and 150 sx cement.

Maximum pressure 500# and shut in pressure 200#

Signed J. A. Mof
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 10:30 am Day: 4 Month: May Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2 set at 4706' Top perf 4654-59

1st plug sand back to 4600' and dump 4 sx cement on top of sand through bailer,

2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 2 sx hulls

and 150 sx cement

Maximum pressure 500# and shut in pressure 200#

Remarks: They recovered 2000' of 4 1/2" casing. Use 60/40 Pozmix 2% gel 3% cc by Allied

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~did not~~) observe this plugging.

INVOICED

DATE 5-14-84

INV. NO. 1502

RECEIVED
STATE CORPORATION COMMISSION
MAY 11 1984
CONSERVATION DIVISION
Wichita, Kansas

Signed J. A. Mof
(TECHNICIAN)