

To: 1 031130
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1-8
API NUMBER 15- 151-22,027 -00-00 37R
C E/2, SEC. 22, T 29 S, R 13 W/E
2640 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5135
Operator: John O. Farmer
Name & Address: P.O. Box 352
Russell, KS 67665

Lease Name Lee Well # 6
County Pratt 151.61
Well Total Depth 4665 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 252

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Emphasis Oil Operations License Number 8241

Address Box 819, Russell, KS 67665

Company to plug at: Hour: 9 a.m. Day: 8 Month: 1 Year: 19 91

Plugging proposal received from Bill Owens

(company name) Emphasis Oil Operations (phone) 913-483-3518

was: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 750'

- 1st plug at 780' with 50 sx cement, 2nd plug at 300' with 50 sx cement,
- 3rd plug at 40' with 15 sx cement,
- 4th plug to circulate rathole with 15 sx cement,
- 5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 11:30 a.m. Day: 8 Month: 1 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 780' with 50 sx cement,

- 2nd plug at 300' with 50 sx cement,
- 3rd plug at 40' with 20 sx cement,
- 4th plug to circulate rathole with 15 sx cement,
- 5th plug to circulate mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
JAN 11 1991
01-11-91
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Steve Durrant (TECHNICIAN)

DATE 2-11-91
INV. NO. 30657

EFFECTIVE DATE: 12-15-90

15-151-22027-0000

FORM MUST BE TYPED
FORM C-1 4/90

State of Kansas
NOTICE OF INTENTION TO DRILL

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 12 month 20 day 90 year

C. E/2 Sec 22 Twp 29 S, Rg 13 East West

OPERATOR: License # 5135
Name: John O. Farmer, Inc.
Address: P.O. Box 352
City/State/Zip: Russell, KS 67665
Contact Person: Sam Farmer
Phone: (913) 483-3144

2640 feet from South line of Section
1320 feet from East line of Section

(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 8241
Name: Emphasis Oil Operations

County: Pratt
Lease Name: Lee Well #: 6
Field Name: Jem
Is this a Prorated Field? yes no
Target Formation(s): Simpson
Nearest lease or unit boundary: 1320'
Ground Surface Elevation: 1859 feet MSL
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no
Depth to bottom of fresh water: 150'
Depth to bottom of usable water: 180'
Surface Pipe by Alternate: 1 2
Length of Surface Pipe Planned to be set: 220'
Length of Conductor pipe required: none
Projected Total Depth: 4700'
Formation at Total Depth: Arbuckle
Water Source for Drilling Operations: from pond other

Well Drilled For: Well Class: Type Equipment:
 Oil ... Inj ... Infield Mud Rotary
... Gas ... Storage Pool Ext. ... Air Rotary
... OAWO ... Disposal ... Wildcat ... Cable
... Seismic; ... # of Holes

If OAWO: old well information as follows:
Operator:
Well Name:

2 w saw
1/2 RECEIVED
STATE CORPORATION COMMISSION

JAN 11 1991

CONSERVATION DIVISION
Wichita, Kansas

Pusher Bill Over
SPUD DATE 12-27 INIT.
LENGTH SURFACE PLANNED 220 + 10 3/4
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED 3 AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 1/2 @ 252 CONDUCTOR
ANHYDRITE T-75 B-720 ELEVATION
TD 4665 FORMATION Arb.
RAN PIPE @ SX DV TOOL SX ALT II DONE Y N
1 Arbuckle Plug @ 50' Arb Ft. W/ 50 SX
2 Anhydrite Base @ 780 Ft. W/ 50 SX
3 1/2 Base Anyh. @ 780 Ft. W/ 50 SX
3 1/2, 1/2 Plug @ 780 Ft. W/ 50 SX
3 Bottom Surface @ 300 Ft. W/ 50 SX
4 40' Plug @ 40 Ft. W/ 20 SX
RAT HOLE CIRC/W/ 5 SX MOUSE HOLE W/ 10 SX
WATER WELL SX (Irr. Well Pond Hauling)
TECHNICIAN SD DATE 1/4/91
TYPE OF CEMENT 60/40 Poz 67% gel
STARTING TIME 9:00 (AM/PM) DATE 1-8-90
COMPLETION TIME 11:30 (AM/PM) DATE 1-8-90
CEMENT COMPANY Allied