

DEC 9 1988

1 040204

T6:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21, 328 - 00-00
60' SE of
C SE SE, SEC. 21, T 29 S, R 13 W/E

630' feet from S section line
630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name Novotny Well # 1-21

Operator: Texas Energies, Inc.

County Pratt 156.00

Name & Address P.O. Box 947

Well Total Depth 4800 feet

Pratt, KS 67124

Conductor Pipe: Size 16 feet 48

Surface Casing: Size 8 5/8 feet 381

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service Inc. License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 10 a.m. Day: 9 Month: 12 Year: 19 88

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service Inc. (phone) 316-672-2531

were: 4 1/2" at 4776' PBSD 4735' Perfs at 4544-4554'

1st plug sand back to 4430' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:45 a.m. Day: 9 Month: 12 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4443' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

RECEIVED STATE CORPORATION COMMISSION

Maximum pressure 500 psi and shut in 250 psi.

DEC 13 1988

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2130' of 4 1/2" casing. (if additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION

observe this plugging.

Signed Stephen J. Pfeifer (TECHNICIAN)

NOTICED

DATE 12-13-88

INV. NO. 23338 12-9