

1 010033

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,515 -00-00  
C NE SE, SEC. 21, T 29 S, R 13 W/EX  
1980 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5004  
Operator: Vincent Oil Co.  
Name & Address 125 North Market, Suite 1110  
Wichita, KS67202

Lease Name Novotny Well # 1  
County Pratt 156.16  
Well Total Depth 4805 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 431

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105  
Address P. O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:00 am Day: 19 Month: September Year: 19 85

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: 4 1/2" at 4791' PRTD 4686' Perfs at 4552-58', 4470-76', 4267-68'

1st plug sand back to 4215' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 100 sx cement.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:25 am Day: 19 Month: September Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4215' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 100 sx cement.

Maximum pressure 500 psi and shut in 250 psi

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 3300' 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

DATE 9-30-85

INV. NO. 10295

CONSERVATION DIVISION  
Wichita, Kansas

SEP 27 1985  
Signed

*Joel R. Smith*  
(TECHNICIAN)