

1 040515

2-18

API NUMBER 15-151-21,060-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

App. SW SW NW, SEC. 20, T 29 S, R 13 W/E

2970 feet from S section line

5000 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9069

Lessee Name Mills Well # 1-A

Operator: General Oil Company, Inc.

County Pratt 153.40

Name & Address 1540 N. Broadway, #202

Well Total Depth 4720 feet

Wichita, KS 67214

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 290

Abandoned Oil Well Gas Well X Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers License Number 4635

Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9:15 a.m. Day: 18 Month: 2 Year: 19 91

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 4 1/2" at 4719', Perfs at 4400-12'

1st plug sand back to 4350' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 5 sx hulls, 20 sx gel, and 175 sx cement.

STATE OF KANSAS RECEIVED
2-28-91
FEB 28 1991

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10 a.m. Day: 18 Month: 2 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4350' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 10 3/4" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 10 3/4" wiper plug and pumped 125 sx cement.

Maximum pressure 750 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2612' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 3-11-91

Signed Stephen J. Pfeiffer (TECHNICIAN)

INV. NO. 31082