

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-151-20234-00-04  
Spot: CS2NESW Sec/Twnshp/Rge: 18-29S-13W  
1650 feet from S Section Line, 1980 feet from W Section Line  
Lease/Unit Name: HARRIS Well Number: 2  
County: PRATT Total Vertical Depth: 4584 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 SOUTH MAIN STE 200  
WICHITA, KS 67202

Conductor Pipe: Size feet: 2 1/4 8.98  
Surface Casing: Size 8.625 feet: 401  
Production: Size 5.5 feet: 4580 WITH 150 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/21/2002 3:25 PM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: VERNON PFLUGHOEFT Company: D S & W WELL SERVICING, INC. Phone: (316) 587-3361

Proposed Plugging Method: SET CIBP @ 3850' WITH 2 SX CMT. 1ST PLUG AT 800' WITH 50 SX CMT. 2ND PLUG AT 430' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT. USE 10 SX GEL FOR SPACER.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 03/21/2002 4:45 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

PERFS AT 3908-18, 4216-19, 4549-51, 4554-64'. CIBP @ 3850' WITH 2 SX CMT ON TOP. 1ST PLUG SPOT 10 SX GEL & 50 SX CMT AT 790'. 2ND PLUG AT 416' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT. GOOD CIRCULATION.

RECEIVED  
MAR 25 2002  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND ACID & CEMENT. RECOVERED 2150' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Scott Alberg

(TECHNICIAN)

INVOICED

MAR 22 2002

Form CP-2/3

DATE

3-26-02

INV. NO.

2002061566

MP