

1050401

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,524 -00-00 *LR*
100' W 110' S of _____
NE NE SE _____, SEC. 6 _____, T 29 _____ S, R 13 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5234

2200 feet from (S) section line
440 feet from (E) section line

Operator: Penguin Petroleum, Inc.
Name & Address 1250 Kansas State Bank Building
Wichita, KS 67202

Lease Name _____ Leak _____ Well # 1
County Pratt
Well Total Depth 4600 *149.50* feet
Conductor Pipe: Size _____ feet ✓
Surface Casing: Size 8 5/8 feet 361

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Rains & Williamson Oil Co., Inc. License Number 5146
Address 435 Page Court, 220 W. Douglas, Wichita, KS 67202

Company to plug at: Hour: 4:00 am Day: 13 Month: December Year: 19 84

Plugging proposal received from Bill Chance

(company name) Rains & Williamson (phone) 316-265-9686

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 810' with 50 sx cement

2nd plug at 390' with 40 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by *Richard W. Lacey*
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 4:45 am Day: 13 Month: December Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 810' with 50 sx cemet, 2nd plug at 390' with 40
sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface
with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form.)

(Do not) observe this plugging.

DATE *12-26-84*

INV. NO. *6170*

Signed *Richard W. Lacey*
(TECHNICIAN) *510*

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas
DEC 18 1984

12-13 JAN 14 1985