

1080206

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,472 -00-00

SW SE NE, SEC. 5, T 29 S, R 13 W/4
N SE Corner of
2970 feet from ~~XXX~~ section line
W SE Corner of
990 feet from ~~XXX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5601

Lease Name Hertlein Well # 1

Operator: Associated Petroleum Consultants, In County Pratt

Name & Address Suite 600 - One Main Place
Wichita, KS 67202-1399

Well Total Depth 4720 153.40 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 337

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SHD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Dunne-Gardner Petroleum, Inc. License Number 5426

Address 200 West Douglas, Suite 250, Wichita, KS 67202

Company to plug at: Hour: 11:00 am Day: 3 Month: September Year: 19 84

Plugging proposal received from Don Tanner

(company name) Dunne-Gardner (phone) 316-265-1611

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 4660' with 40 sx cement

2nd plug at 830' with 50 sx cement

3rd plug at 390' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement
Plugging Proposal Received by J. H. Metz

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1:30 pm Day: 3 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 4660' with 40 sx cement, 2nd plug at 830' with 50 sx

cement, 3rd plug at 390' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole

with 10 sx cement.

STATE CORPORATION COMMISSION

SEP 11 1984 9-11-84

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun

(If additional description is necessary, use BACK of this form.)

I (did not) observe this plugging.

INVOICED

DATE

9-14-84

INV. NO.

3653

Signed

J. H. Metz
(TECHNICIAN)

SO