

To: 1 126807  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

7-21

API NUMBER 15-151-20,733-00,00  
E/2 NE SE, SEC. 3, T 29 S, R 13 W/8  
1980 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30323  
Operator: P G & E Resources Company  
Name & Address: 6688 N. Central Expwy., Ste. 1000  
Dallas, TX 75206-3922

Lease Name Stevens Well # 1  
County Pratt  
Well Total Depth 4775 155.18 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 331

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524-0347

Company to plug at: Hour: 10 a.m. Day: 21 Month: 7 Year: 19 93

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

logs: 4 1/2" at 4766' w/150 sx cement, PBTD 4760', Perfs at 4626-30, 4514-18'

- 1st plug pump 100 lbs. hulls and 30 sx common cement.
- 2nd plug pump in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:30 a.m. Day: 21 Month: 7 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug pumped 100 lbs. hulls and 30 sx cement, displaced to 4450',  
2nd plug pumped in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 1000 psi and shut in 100 psi.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 27 1993

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2802' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 7-28-93  
BY: 38214

Signed *Duan Rankin*  
(TECHNICIAN)

CONSERVATION DIVISION  
Wichita, Kansas