

9-14-87

1 061001

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,013 - 00-00
SE. SE. SE. SEC. 3, T 29 S, R 13 W. 1/4
440 feet from S section line
440 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4934
Operator: Tarrant Operators, Inc.
Name & Address: 6212 Indian Creek Dr.
Fort Worth, TX 76107

Lease Name Stevens Well # 2
County Pratt
Well Total Depth 4774 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 535

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 4 p.m. Day: 14 Month: 9 Year: 1987

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 4773' Perfs at 4730-36' PBTD 4754' Elevation 1924' GL

1st plug sand back to 4680' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 130 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5 p.m. Day: 14 Month: 9 Year: 1987

ACTUAL PLUGGING REPORT 1st plug sanded back to 4680' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 130 sx cement.

Maximum pressure 700 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2568' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Paul A. Luthi (TECHNICIAN)

DATE 9-23-87

INV. NO. 18181

9-17-87
1987
Rev. 17/20
SEP 12 1987