

To: 120722
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

7-31 API NUMBER 15- 151-22,013 - 00-002 30 R
30' S of
NW NE NE, SEC. 17, T. 29, S. R. 13 W/R

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056
Operator: F.G. Holl Company
Name & Address P.O. Box 780167
Wichita, KS 67278-0167

4920 feet from S section line
990 feet from E section line
Lease Name Omo Well # 1-17
County Pratt 157.88
Well Total Depth 4858 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 13 3/4 feet 277

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893
Address P.O. Box 847, Pratt, KS 67124-0847

Company to plug at: Hour: 11 a.m. Day: 31 Month: 7 Year: 1992

Plugging proposal received from Bruce Wagner
(company name) Pratt Well Service (phone) 316-672-2531

were: 4 1/2" at 4856' w/225 sx cement, PBTB 4600', Perfs at 4709-18, 4610-28, 4522-60'
1st plug sand back to 4380' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 175 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 12:30 p.m. Day: 31 Month: 7 Year: 1992

ACTUAL PLUGGING REPORT 1st plug sanded back to 4380' and dumped 4 sx cement on top of sand
bridge through bailer,
2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 175
sx cement.

Maximum pressure 200 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2299' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 8-10-92
INV. NO. 35-914

Signed David Rankin
(TECHNICIAN)

RECEIVED
CORPORATION COMMISSION
AUG 4 1992
CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION

AUG 4 1992

CONSERVATION DIVISION
Topeka, Kansas