

1040166

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION C S/2 SW NW, SEC. 14, T 29 S, R 13 W/E  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,505 -00-60 R

2970 feet from N/S section line  
4545 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9069

Lease Name Wray Well # 1-A

Operator: General Oil Company  
Name & Address 909 West 14th  
Wichita, KS 67203

County Pratt 155.68

Well Total Depth 4790 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 770

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A  X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor H-30 Drilling, Inc. License Number 5107

Address 251 North Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 10:00 am Day: 10 Month: December Year: 19 84

Plugging proposal received from E. J. Woody

(company name) H-30 (phone) 316-263-2043

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 825' with 60 sx cement

solid bridge

2nd plug hulls - plug at 40' -- cement to surface with 10 sx cement

RECEIVED

STATE CORPORATION COMMISSION

4th plug to circulate rat hole with 15 sx cement

DEC 12 1984

5th plug to circulate mouse hole with 10 sx cement

CONSERVATION DIVISION

Plug water well with 5 sx cement  
Plugging Proposal Received by Ed Knobloch Wichita, Kansas

(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None  X

Operations Completed: Hour: 12:15 pm Day: 10 Month: December Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 825' with 60 sx cement, 2nd & 3rd plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 4th plug to circulate rat hole with 10 sx cement, 5th plug to circulate mouse hole with 10 sx cement, and plugged water well with 5 sx cement

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Sun  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-18-84

INV. NO. 5997

Signed  (TECHNICIAN)