

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-157-21,334-00-00

NW/4, Sec. 10, T 29 S, R 12 W

1980 feet from N/X section line

660 feet from W/X section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5538

Lease Name PRATT MILLER Well # 1

Operator: TOM KAT LTD.
Name & P.O. BOX 18122
Address WICHITA, KS 67218

County PRATT

Well Total Depth 4708 feet 153.01

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 263

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor ALDEBARAN DRILLING CO., INC License Number 5829

Address 453 S. WEBB ROAD, SUITE 100, BOX 1864, WICHITA, KS 67202

Company to plug at: Hour: 3:00 PM Day: 31 Month: OCT Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO LARRY HARRIS

(company name) ALDEBARAN (phone)

were: to use 60/40 Pozmix w/2% gel - 3% CC AND SPOT
1ST plug @ 4659 w/30 SF; 2ND plug @ 820' w/50 SF;
3RD plug @ 320 w/50 SF; 4TH plug @ 40' w/solid bridge
and 10 SF cmt; Circulate 15 SF in rat hole and
10 SF in mouse hole. Plug water well w/5 SF. Orders
by Ed Knobloch

Signed R. B. Barbutan
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 6:45 PM Day: 31 Month: OCT Year: 1983

ACTUAL PLUGGING REPORT plugged as ordered. Cementing
by Sun. Deckett #15611.

Remarks: An agent could have attended this, but original
plug time to begin was given as midnight and pusher
failed to call in the new start time.

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / did not) observe this

INVOICED

DATE
INV. NO. 6078-W

STATE CORPORATION COMMISSION

NOV 3 1983

CONSERVATION DIVISION
Wichita, Kansas

Signed R. B. Barbutan
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82

11-3-83