

1 040343

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-20,983-0D-0D
NE SE NW, SEC. 7, T 29 S, R 12 W/E
3630 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050

Lease Name Mueller Well # 1

Operator: Hummon Corporation
Name &
Address 400 One Main Place.
Wichita, KS 67202

County Pratt 152.13

Well Total Depth 4681 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 214

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893

Address Box 847, Pratt, KS 67124

Company to plug at: Hour: 9:45 a.m. Day: 27 Month: 10 Year: 19 89

Plugging proposal received from Kenny Gates

(company name) Pratt Well Service (phone) 316-672-2531

were: 4 1/2" at 4670' PBTd 4304' Perfs at 4217-20, 4256-60, 4476-82, 4676-81' Elevation 1901'
1st plug sand back to 4165' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, 100 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 a.m. Day: 27 Month: 10 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4120' and dumped 4 sx cement on top of sand bridge with bailer,

2nd plug pumped down 10 3/4" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 125 sx cement.

Maximum pressure 150 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 10% gel by B.J. Titan. Recovered 2829' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 11-2-89

INV. NO. 2630V

10-27

Signed Stephen J. Pfeifer
(TECHNICIAN)