

To: 1 040025  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

12-9-87  
API NUMBER 15-151-21,140-00-00  
SW SW SE, SEC. 7, T 29 S, R 12 W/EX  
330 feet from S section line  
2310 feet from E section line  
Lease Name Reece Well # 1  
County Pratt 152.75  
Well Total Depth 4700 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 13 3/8" feet 237

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050

Operator: Hummon Corporation  
Name & Address 400 One Main Place  
Wichita, KS 67202

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address 107 West Fowler, Medicine Lodge, KS 67104

Company to plug at: Hour: 1:50 p.m. Day: 9 Month: 12 Year: 19 87

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4567' PRTD 4400' Perfs at 4456-60, 4337-40, 4156-60, 3926-31'

1st plug sand back to 3875' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 5 sx hulls and 170 sx Econolight.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:20 p.m. Day: 9 Month: 12 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back from 4400' to 3875' with 4 sx cement on top of sand with dump bailer,

2nd plug pumped down 13 3/8" surface casing with 500 lbs. hulls and 170 sx cement.

Pumping pressure 100-300 psi and shut in 100 psi.

Remarks: Used Thrifty Mix cement by B.J. Titan. Recovered 2300' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED  
(circle / XXXXXXX) observe this plugging.

DATE 12-15-87

SER. NO. 19289

Signed Stephen J. Pfeifer  
(TECHNICIAN)

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas  
DEC 14 1987 12-14-87