

11-2 15.15-21757-00-00

To: 1 040182
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 1/10/86

NW NW NE, SEC. 23, T 29 S, R 11 W/E_X

TECHNICIAN'S PLUGGING REPORT

RECEIVED
STATE CORPORATION COMMISSION

4950 feet from S section line

2310 feet from E section line

Operator License # 4933 Lessee Name Farmer Well # 1

Operator: VAC Petroleum Company County Pratt 154.38

Name & Address P.O. Box 780106 Wichita, KS 67278

NOV 14 1988
CONSERVATION DIVISION
Wichita, Kansas

Well Total Depth 4750 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 424

Abandoned Oil Well Gas Well _____ Input Well _____ SHD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 12:15 p.m. Day: 2 Month: 11 Year: 19 88

Plugging proposal received from Roger Loesch

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 4748' Perfs at 4071-4658' (5 sets)

1st plug sand back to 4020' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1 p.m. Day: 2 Month: 11 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4000' and dumped 5 sx cement on top of

sand through bailer.

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,

100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 200 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2500' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
(did / did not) observe this plugging.

DATE 11-21-88

INV. NO. 23054

Signed Stephen J. Pfeifer (TECHNICIAN)