

1090195

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,448-00-00

C SW NE, SEC. 27, T 29 S, R 11 W X

1980 feet from N/W section line

1980 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Hakanson Well # 1-27

Operator: F. G. Holl

County Pratt

Name & Address 6427 East Kellogg

Well Total Depth 2790 <sup>90.6%</sup> feet

Wichita, KS 67207

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 265

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sterling Drilling Company License Number 5142

Address P. O. Box 129, Sterling, KS 67579

Company to plug at: Hour: 3:30 pm Day: 21 Month: June Year: 19 84

Plugging proposal received from Tom Myers

(company name) Sterling (phone) 316-672-5663

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 960' with 60 sx cement

2nd plug at 330' with 40 sx cement  
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement  
Plugging Proposal Received by R. Starbuckton

(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 5:45 pm Day: 21 Month: June Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 960' with 60 sx cement, 2nd plug at 330' with 40 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to circulate mouse hole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

07-02-84 JUL 06 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc  
(If additional description is necessary, use BACK of this report.)  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

DATE 7-11-84

INV. NO. 2389

Signed R. Starbuckton  
(TECHNICIAN)