

3-14 80
API NUMBER 15- 151-20,724 - DD-00
NW SE SW, SEC. 34, T 29 S, R 11 W/E
990 feet from S section line
3630 feet from E section line

To: 1 040237
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056
Operator: F.G. Holl Company
Name & Address: P.O. Box 780167
Wichita, KS 67207
County: Pratt
Lease Name: Miller "C" Well # 1-34
Well Total Depth: 2800 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 7" feet 251

RECEIVED
STATE CORPORATION COMMISSION
03-21-89
MAR 21 1989
CONSERVATION DIVISION
Wichita, Kansas

91.00

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor: Pratt Well Service License Number 5893

Address: P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 9:45 a.m. Day: 14 Month: 3 Year: 19 89

Plugging proposal received from: Bruce Wagner

(company name) Pratt Well Service (phone) 316-672-2531

were: 4 1/2" at 2793' PBTD 2760' Perfs at 2719-41' TOC at 1950'

1st plug sand back to 2650' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 400 lbs. hulls, 8 sx gel, 40 sx cement, 8 sx gel, 100 lbs. hulls, release

7" wiper plug and pump 100 sx cement.

Plugging Proposal Received by: Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 a.m. Day: 14 Month: 3 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 2590' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 7" surface pipe with 400 lbs. hulls, 8 sx gel, 40 sx cement, 8 sx gel, 100 lbs. hulls, and 82 sx cement.

Maximum pressure 1600 psi and shut in 1150 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 1782' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 3-23-89

INV. NO. 24194

Signed: Stephen J. Pfeifer (TECHNICIAN)