

To: 1 041169
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 151-20,695 -00-00
C NW, SEC. 33, T 29 S, R 11 WEX
3960 feet from S section line
3960 feet from E section line

4-25

TECHNICIAN'S PLUGGING REPORT
Operator License # 5447
Operator: OXY USA Inc.
Name:
Address 110 S. Main, Ste. 800
Wichita, KS 67202

Lease Name Knop A Well # 1
County Pratt 92.59
Well Total Depth 2849 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 255

Abandoned Oil Well Gas Well X Input Well SWD Well O&A
Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105
Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10 a.m. Day: 25 Month: 4 Year: 1996

Plugging proposal received from Alan Vratil
(company name) Clarke Corporation (phone) 316-886-5665

work: 4 1/2" at 2849' w/100 sx cement, PSTD 2807', Perfs at 2760-68, 2620', CIBP @ 2740'
1st plug sand back to 2530' and dump 4 sx cement on top of sand through bailer,
2nd plug at 720' with 50 sx cement, 3rd plug at 280' with 40 sx cement,
4th plug at 40' with 10 sx cement,

04-31-96

Plugging Proposal Received by Kevin Strube
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None
Operations Completed: Hour: 11:15 a.m. Day: 25 Month: 4 Year: 1996

ACTUAL PLUGGING REPORT 1st plug sanded back to 2530' and dumped 4 sx cement on top of sand
bridge through bailer,
2nd plug ran 2 3/8" tubing in hole to spot plugs through and loaded hole with gel. Spotted
50 sx cement at 705',
3rd plug spotted 40 sx cement at 276',
4th plug at 40' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2150' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED (if desired, check box to observe this plugging.)

DATE MAY 06 1996
TV. NO. 45525

Signed Stephen J. Pfeiffer
(TECHNICIAN)

RECEIVED
KALISAS
1996 APR 28