

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-21117-00-00
Spot: CNWNWSW Sec/Twnshp/Rge: 33-29S-11W
2970 feet from N Section Line, 330 feet from W Section Line
Lease/Unit Name: ROLF Well Number: 1-33
County: PRATT Total Vertical Depth: 2815 feet

Operator License No.: 5056
Op Name: HOLL, F.G., COMPANY L.L.C.
Address: 6427 EAST KELLOGG
WICHITA, KS 67207

Conductor Pipe: Size feet: # 91.49
Surface Casing: Size 8.625 feet: 264 WITH 200 SX CMT
Production: Size 4.5 feet: 2815 WITH 125 SX CMT
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 11/13/2001 12:50 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND BACK TO 2685' & 4 SX CMT. 1ST PLUG AT 710' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 295' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/13/2001 1:45 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:


PERFS AT 2755-2759'. SAND BACK TO 2685' & 4 SX CMT ON TOP WITH BAILER. 1ST PLUG AT 710' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 295' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 2041' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED

NOV 21 2001

KCC WICHITA

INVOICED

NOV 20 2001

DATE 11-26-01

INV. NO. 2002060970

