



DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 10-25

LOCATION SE-SW-SW

SEC. 7 TWP. 29 RGE. 12-W

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 2-A Lease Stacks

Operator Bridgport Oil Co Address #914-Central Bldg-Wichita-Kans-

Field \_\_\_\_\_ County Pratt

Total Depth 4562 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/8 - 859 ft - Circulated with Cement -  
5 1/2" casing Set at 4494 ft - Filled back from bottom  
with mud to 3900 ft - Rock Bridge & 15 sacks of Cement  
at 3900 ft - Pulled 3 1/2" casing & Mud to 850 ft - Bridge  
& 15 sacks of Cement - Mud to 200 ft - Bridge & 15 sacks  
of Cement - Mud to 20 ft - Bridge & 10 sacks of Cement -  
Worgett & Lynch - Pipe Pulling Contractors

APR 19 1948  
04-19-48

C. H. Stouch  
District Conservation Agent

Date 4-16-48

**PLUGGING**  
FILE SEC 7-29-R-120  
BOOK PAGE 101-25