

KANSAS

STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name McClure Oil Company  
 Complete Address: 1301 Wichita Plaza Bldg., Wichita, Kansas  
 Lease Name Inslee Well No. # 1  
 Location NW NW SW Sec. 23 Twp. 29 Rge. 11 (E) (W) W  
 County Pratt Total Depth 4691'  
 Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X  
 Other well as hereafter indicated:       
 Plugging Contractor: Lauck Drilling Company, Inc.  
 Address: 301 South Broadway, Wichita, Kansas License No.       
 Operation Completed: Hour 9:30PM Day 24th Month July Year 1966

The Above well was plugged as follows:

411' of 8 5/8" surface pipe, cement circulated with 320 sacks. Hole was  
filled with drilling mud to 300', 1st cementing plug, bridged with 2 sacks  
of dry cement, and 1/2 sack of hulls on fluid at 300', and cemented with  
25 sacks. Hole was filled with drilling mud to 40', 2nd cementing plug,  
bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid at 40',  
and cemented with 9 sacks to the base of the cellar. Rat hole bridged and  
cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving  
Well Plugging Supervisor

INVOICED

DATE 7/28/66  
INV. NO. 3641-W