

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

R

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - - (of this well)

Operator's Full Name Ronald Russ Prather, Inc.

Complete Address 240 Rock Road, Suite 235, Wichita, Ks.

Lease Name Rolf Well No. 1

Location SW NE NE Sec. 34 Twp. 29 Rge. 11 (E) (W) X

County Pratt Total Depth 2945

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Rockhold Engineering Inc.

Address Box 698-Great Bend, Ks. 67530 License No. 670

Operation Completed: Hour 11:45 Am. Day 22 Month 1 Year 1980

The above well was plugged as follows:

301' 8 5/8" casing w/275 sax cement. 4 1/2" casing set at 2897' w/150
sax cement. Plug back to 2725'-Preforated at 2707' to 2725'-Sand back
to 2675'-Top sand w/4 sax mixed cement w/dump bailer. Pull 2000* 4 1/2"
casing-Allied mixed & pumped 8 sax hulls-25 sax gel-100 sax 50/50
posmix cement w/4% gel & 3%cc to top of casing. Shut in w/400# pressure

RECEIVED
STATE CORPORATION COMMISSION

JAN 25 1980

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 1-25-80

INV. NO. 1405-w