



15-097-10166-0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

NOV 8 1965

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Bill Draper of Gabbert-Jones, Inc. has this date requested permission to plug the following described well:

Mr. Draper guarantees payment of the plugging fee.

Operator's full Name: J. Mark Richardson & Earl S. McCandless

Complete Address: 502 Union Center, Wichita, Kansas

Lease Name: Seacat Well No. # 1

Location: C SE NE Sec. 23 Twp. 28 Rge. 19 (E)(W) W

County Kiowa Total Depth 4946' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Draper was instructed to plug the well as follows:

310' of 8 5/8" surface pipe, cement circulated with 235 sacks.

Fill hole with drilling mud to 275', 1st cementing plug, bridge

with hulls, and cement with 25 sacks. Fill hole with drilling mud

to 40', 2nd cementing plug, bridge with hulls, and cement with 10

sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent