

State of Kansas



15-097-10218-0000

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 29 1966  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Bill Draper of Gabbert-Jones, Inc. has this date requested permission to plug the following described well:

Mr. Draper guarantees payment of the plugging fee.

Operator's full Name: Leo Michaelis

Complete Address: R. R. # 2, Russell, Kansas

Lease Name: Copeland Well No. # 1

Location: C SW SE Sec. 7 Twp. 28 Rge. 19 (E)(W)W

County Kiowa Total Depth 4970' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Draper was instructed to plug the well as follows:

351' of 8 5/8" surface pipe, cement circulated with 240 sacks. Fill hole with drilling mud to 275', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Arlie Elving  
Conservation Division Agent