



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. - 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 APR 2 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

15-097-30012-00-01

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

March 20, 1968.

Dear Sir:

Mr. D. B. Pulley of Forbes Caseing Pulling Inc. this date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: Woods Petroleum Co.

Complete Address: Box 18667 Oklahoma City, Oklahoma 73118

Lease Name: Pyle Well No. #2

Location: C-NE-SE Sec. 2 Twp. 28S Rge. 19 (E)(W) W

County: Kiowa Total Depth 4918 Oil Well Abd

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Pulley was instructed to plug the well as follows:

4918 ft of 4 1/2" long string. Top perforation at 4853 ft. Sand  
to 4700 ft. & 4 sacks cement. 361 ft. of 8 5/8" surface pipe  
circulated with cement. Mud to 350 ft., 10 ft. rock bridge  
& 25 sacks cement. Mud to 40 ft., 10ft. rock bridge & 10 sacks  
cement to surface. 2930 ft. of 4 1/2" pipe pulled.

Very truly yours,

*Harmon Justice*  
 Conservation Division Agent



ROBERT B. DOCKING Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
DALE E. SAFFELS Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-097-30012-00-01

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Wade of Woods Woods Petr. has this date requested permission to plug the following described well:

Mr. Wade guarantees payment of the plugging fee.

Operator's full Name: Woods Petroleum Corp.

Complete Address: Box 18667, Oklahoma City, Okla. 73118

Lease Name: Pyle Well No. 2

Location: CNESE Sec. 2 Twp. 28S Rge. 19W(2)(W)

County: Kiowa Total Depth 4918 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Wade was instructed to ~~plug the well as follows:~~

Fisher Casing Pulling Co. Lic. 49  
obtained plugging instructions  
from Mr. Justice

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 15 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Very truly yours,

S. S. Greenlee

Conservation Division Agent