



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

5-April 1982

RECEIVED
STATE CORPORATION COMMISSION

APR 13 1982

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

75-057-2060-0000

Dear Sir:

4-13-1982

Mr. Herbert French of Pickrell Drilling Co. has this date requested permission to plug the following described well:

Operator's Full Name: Pickrell Drilling Co.

Complete Address: Sitwin Bldg. Suite 205 Wichita Kans.

Lease Name: Berty Well No. 1-B

Location: NW-SW-SE Sec. 34 Twp. 29 Rge. 22 (E) (41)

County: Lea Total Depth: 5425'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. French was instructed to plug the well as follows:

They cement circulated 299' of 8 5/8" surface casing with 200 Sbk of common cement 2% Jell & 3% C.C. 1st plug at 960' with 70 Sbk of cement. 2nd plug at 270' with 40 Sbk of cement. 3rd plug at 40' to 0' with 10 Sbk of cement. Then circulated 10 Sbk of cement in rat hole. The cement used was 50/50 gauge with 4% Jell & 3% C.C. Allied cementing completed the plugging.

Very truly yours,

Paul G. Luthis
Conservation Division Agent