

State of Kansas



FORM CP-2

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

20 March 1982

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Ray Kager of Samuel Gary Oil Pro. has this date requested permission to plug the following described well:

Operator's Full Name: Samuel Gary Oil Producers

Complete Address: 100 Military Plaza, Dodge City Kans 67801

Lease Name: Cuer "A" Well No. 1

Location: NE "NW" Sec. 28 Twp. 29 Rge. 22 (E) (M)

County: Ford Total Depth: 5425'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Kager was instructed to plug the well as follows:

They have 304' of 5" surface casing cement circulated. They have 5400' of 5 1/2" production pipe set. They had plugged back to 5360' and perforated pipe at 5253' to 62'. They had hole in production pipe at 804' and squeezed it with 125 lbs of cement with 2500 lbs pressure. They ran a bonding log today on ~~production~~ pipe it was bonded from 726' to 858'. So they perforated pipe at 720' and pressured

Very truly yours,

RECEIVED
STATE CORPORATION COMMISSION

MAR 23 1982

CONSERVATION DIVISION
Wichita, Kansas

Paul A. Luttich
Conservation Division Agent

up with water and circulated water to top between surface casing & production pipe. 1st plug pumped 225 lbs of cement on bottom hole with 2 lbs of hulls ahead of cement. 2nd plug set cast iron plug at 820'. Then perforated production pipe at 120' and circulated water to top between surface casing & production pipe. 3rd plug pumped 275 lbs of cement between surface ^{through} pipe & production pipe till cement surfaced & filled both pipes to 0'. Plugging was accomplished by Halliburton Co.