



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

3 - November 1981

RECEIVED
STATE CORPORATION COMMISSION

NOV 10 1981

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

15-057-20245-0000

CONSERVATION DIVISION
Wichita, Kansas

11-10-1981

Dear Sir:

Mr. Rod Randell of Salvadoro Drilling Co. has this

date requested permission to plug the following described well:

Operator's Full Name: Sam Gary Oil Co.

Complete Address: 4 Sumerne Court East Englewood Colo. 80112

Lease Name: Honer Well No. 10-7

Location: C-SW-NE Sec. 10 Twp. 29S Rge. 22W(E) (W)

County: Ford Total Depth: 5335'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Randell was instructed to plug the well as follows:

There is 575' of 8 5/8" surface casing cement circulated. The lubricator was taped at 1776'. All fresh water formations are behind surface casing. 1st plug at 1380' with 70 sbx cement 2nd plug pushed rubber plug to 550' and pumped 40 sbx of cement on top of rubber plug. 3rd plug on solid bridge at 40' to 0' with 10 sbx cement. Then pumped 5 sbx cement to bottom of rat hole. Plugging accomplished by Halliburton Co. out of Pratt Ks.

Very truly yours,

Paul Luthi
Conservation Division Agent